

# PENN HYPERLΨP

# NoDiggity V2

Overall goal was to dig a 30m long horizontal tunnel of 0.5m diameter. I was the Cutterhead and Main Drive systems RE (responsible engineer) for a system that generated 2.2 kNm of torque. Was the de facto mechanical—side team lead and coordinated between the propulsion system, soil removal and ground conditioning systems, to ensure delivery on the machine.

Not mentioned in this portfolio are the numerous hours (~50% of my time) spent planning the logistics of moving and testing ops, organizing a temporary build space, and fighting with school management for recognition, and fundraising talks.

Official dig length of 1.5m to win Rookie Award with smallest team and simplest TBM design (as per judges).

## Excavation Systems - NoDiggity V2 - Penn Hyperloop

### Meain Drive Torque Calculation

Utilizing the findings of Hu's 2011 paper\* we can split up our torque contributions as seen below.

Torque Contribution	Torque (kNm)
T1 (Front)	1.169910308
T2 (Lateral)	0.5114362
T3 (Back)	0.389970103
T5 (Opening Shear)	0.13847143
T6 (Agitating torque)	0.2662796
Total Torque	2.476067639

Using a FOS of 2 we get a recommended Torque of ~5 kNm


**Initial Design – Started off** with main physics requirement of torque needed. Accordingly, sourced sized a gearmotor + custom coupling system that fits into CAD modeled outer structure.


### Key System Metrics: (Rossi Group motor: HB3 132 S 4, Rossi Group planetary gear reducer: EP R 3EL)

- Estimated Output Torque: 4780 Nm
- Nominal Output Speed: 8.1-11.9 rpm Mass: 221 kg
- Effective reduction ratio: 142.56-209.44
- Gearmotor configured for expected axial/thrust loads from manufacturer.

- Custom machined keyway two-piece coupling (Stafford) 316 Stainless Steel
- (for corrosion protection) 6 screws on each side
- Holding Torque: 3723 Nm

- Assuming AISI 4340 242 HR steel with a Young's modulus a plate thickness of of 33mm would be needed to support the system. Considering a safety factor of 1.5, a plate thickness of 49.5mm (50mm) would be desirable.
- Mounting Strategy: Weld ring plate to outer body casing to create a flange mounting system for plate to be bolted to. This allows for removal of plate to make other components accessible.







# **Improved design:**


Overall structural analysis shown for various failure modes.

Added: lifting points, alignment peice to achieve concentrictiy and better torque transfer, switched out gearmotor based on updated assumptions.










### Excavation Systems - NoDiggity V2 - Penn Hyperloop




## **Assembly and Machining Plans generated:**

(Test Plans were skipped due to lack of funding early enough into our process.)

This and other "assembly plan" documents cover any overall assembly that involves more than one component, individual components will be covered in machining plans.

1. Prep with cutterhead + cutters, extended shaft with key + weided alignment piece, outer structure with cutouts, chamber put together (as in all plates weided together and to the back cnc cut part + long steel tube also welded to chamber and going this with petal holes have considered to the proper part to the plate to the proper part to the part to the proper part to the part to t

2. Take back-outer structure gipe, weld motor mounting plate in appropriate location (pictured to left). Filip structure such that plate is at the bottom vertically (pictured to right). Place between two workbenches, lower motor using gantiny crane in with botts hanging from the motor flange holes. Rotate by hand until botts align and go through the plate double for it on the lower side of the halfe.



Take front outer structure pipe, place unfinished muck chamber inside at the appropriate totation (laterally) (picture to the left). Place pipe horizontally alongside the back outer pipe with the culouts halfway in (pictured to right), make the pipe go through the both hole in the motor mount plate. Make tack welds for chamber plate-pipe interface.



On the cutterhead side, place the thinner ring in and weld to muck chamber plates itself. Maybe to the inside of the outer pipe too.



Put coupier onto motor shart roosely. Bring front section it, align the much, time and pass the gos line through the motor mounting plate holes, do not fully push the structures into each other (see image below. Its missing the muck line only.). Come in with the extended shaft from inside the muck chamber until shaft goes fully into coupler. Tighten coupler, push the two sections all the way together, duct tage it.



- Lift up cutterhead using gantry crane, align using alignment tool and put the four bolts
- 7. Done.
- coupler, take extended shaft off, slide front structure off fully, take nut off of motor mounting plate, flip back structure vertically and pull motor out.

ror all of above, we are yet to consider reasibility of litting and rotating and pushing sections of steel around..

Prop/ Launch Structur

- Parts that should be completed and obtained by this point: Back Plate, 3 periodic support plates, 4 launch railing bars, thrust plate and 4 small support plates for the buplate. The appropriate screwiack and motor must also be purchased
- The launch railing will first be assembled by aligning 2 launch railing bars and welding them into a longer railing line. This should be done twice to produce a total to 2 longer launch railing hars.
- 3. The Isunch railing bars should then be welded to the periodic support plates. The first plate can be placed flat on the ground and the Isunch railing bars placed vertically in the slots, stabilized and then welded. Then, the structure is turned in the correct orientation (as seen below), after which each additional plate is slid along the launch railing bars to the appropriate location and held in place, and then welded. This creates the Isunch rails are the sum of the properties of the place is the properties.




4. The back plate structure is then assembled. The 4 small plate supports are wedded to th back plate, holding them flush against a flat surface and welding along the joints. Distances from the corner pieces can be measured and held in place while welding (lateral position accuracy is not exactly required since they just need to go under the concrete blocks.



 The back plate structure must then be welded to the launch railing structure. (not su how to stabilize this but maybe holding everything flush to the ground and using son sort of MDF jig?)

- Screwjack must be slided into the back plate hole using a gantry crane and align the bolt holes for the base of the screwjack, and then be boilted into place. (likely some sort of stoot) babba for the motor to rest on. Might not be a huge issue but co with became it is in babba.
- Thrust Plate must be held (can likely be held by 2 people) and aligned to the top plated on the correlator and then be helded into place.






# Excavation Systems - NoDiggity V2 - Penn Hyperloop Site Layout








# Manufacturing + Assembly at Nextfab (makeshift workspace for the machine)

Learnt and applied flux-core MIG Welding up to 1/4" thickness on Mild Steel.

### **Launch Setup**



- propulsion structure and TBM separately b.Retrieval pit to be dug 10 meters from

### **Retrieval Plans**

- Retrieval pit is dug for our max possible dig length of 11 meters. Once tbm surfaces, all pipes/wires will be disconnected, removable eue bolts will be screwed into the top and lifted out.
- In the event of machine failure before finishing dig, excavator will be required to dig to the depth of tunnel crown, team will dig around the pit to reveal full TBM for

**Biggest Risks** 

Reaction torque causes TBM to spin

Mitigation: Gearmotor can spin in both directions. Will

veen back of TBM and clay pipe resists rotation

An overcut is present where the outer cutters furthest oint leads to an effective 20.5" OD (above the 20" of

Motor mounting plate-outer structure weld failing (since

Unlikely to happen since TBM is heavy + friction

### **Cutterhead & Main Drive**

- Both parts are made of stronger 4340 steel +
- Unlikely since coupler is rated for max-torque expected (with FOS). This torque is likely not required at initial stages of dig either.

Ready to mine?: No

### **Open Action Items**

- Fasten cutters on cutterhead Done at comp to minimize cutter damage
- Mount motor into TBM structure Will be done on Monday, Tuesday latest
- Mount coupler, shaft, cutterhead onto TBM
- Will be done once TBM is assembled and high power

# **Evaluated mining readiness across mechanical systems to** present to overseeing organization (Boring Company)









Coordinated site prep, lifting ops, troubleshooting dig/demo day failures